

ESTIMATE

The Vanlife Collective
1537-B Osprey Dr
Hood River, OR 97031

info@thevanlifecollective.com
+1 (541) 224-6966
https://thevanlifecollective.com



Template

Bill to
Template

Ship to
Template

Estimate details

Estimate no.: 1319
Estimate date: 02/07/2024

Vehicle Type, Height & Length: Transit High Roof
148 Ext
Vehicle Year: 2024
Conversion Package: Adventure Jade

#	Date	Product or service	SKU	Qty	Rate	Amount
1.		Summary Family Jade Package on a Transit 148 Ext Seat 4 Sleep 2 2x Fans 2x Bunk windows 2x Large Slider windows Insulated Floor, Walls and Ceiling, upholstered and with Ltrack at the top corner where walls meet ceiling. Dimmable lights in ceiling, and reading lights at rear. Floor Trim Kit Prewire for lights and fans to standard wheel well location. 480Ah MightyMama battery system 400W Solar Steelhead Galley on Driver Side with Jerry Cans and 86Qt Fridge 22 Gal Craftsman Water Cabinet Built in Outback Shower Bosch 2.5 Gal Hot Water Heater 20 Gal undermount Grey Elevation Station raising bed Espar Heater (4kw gas) Swivel Seats Shark Board B-Pillar Lagun Table Storage: 2x Upper Cabinets, Headliner Shelf Bugwall Screen on slider door opening Vanmade Gear Window Shades all around Exterior: Roof Rack Ladder Surf Pole 270 Awning Front Light Bar Rear Flood Lights		1	\$0.00	\$0.00
2.		Maxxfan 7500 smoke (Installed)	Maxxfan7500_3	2	\$997.50	\$1,995.00

Fan Install Package.
 For the front sprinter fan only, the fan adaptor is removed

3.	Large Window (Installed) Install a window in van body. --VWD Full Driver Slider	LargeWindow	1	\$1,261.95	\$1,261.95
4.	Large Window (Installed) Install a window in van body. --VWD Full Passenger Slider	LargeWindow	1	\$1,261.95	\$1,261.95
5.	Bunk Window (Installed) Install a window in van body.	BunkWindow_3	2	\$844.94	\$1,689.88
6.	Foundation Floor T148std/S144 3/4 Subfloor allows threaded anchors to integrate with our modular assemblies and saves time on the back end. Minicell insulation 3/4 anchored subfloor 2tec2 or Lonseal Flooring Anti-Mold treatment under subfloor Anti-Rust Treatment under anchor points Trim Kit for Step Cubby, Rear and Front edges, or reuse existing step and rear trim. (-\$150, removes extra trim pieces but adds time for building up step)	StdFloor_8	1	\$5,139.36	\$5,139.36
7.	Thinsulate entire van 600L Thinsulate throughout van. Walls, ceiling, slider door and rear doors included. Options to add on: -Double layer (2x\$) -Front doors (+\$450) -Pull Through ceiling ribs (+\$300)	Thins600L_6	1	\$1,601.00	\$1,601.00
8.	Ceiling -- Transit 148 ext (installed) T148ext Split front panel 3x LED, dimmable, with blue night mode. Surface Mount Upholstered to your color choice Optional: add front glow strip +\$599 Standard Front/Rear fan locations optional		1	\$4,599.00	\$4,599.00
9.	Elephant Ear Upholstery - Transit Transit -- Upholster the foam "elephant ears"	Elephant_Transit_4	1	\$599.00	\$599.00
10.	Prewire Lights Prewire 12/2 to light run. Terminates in spade connector at ceiling, integrating with ceiling assembly. Central dimmer or switch optional	Prewire_lightrun2/2.5	1	\$341.88	\$341.88
11.	Transit Wall Package Install a full wall kit -Panels -Ltrack @ top corner -Prewire for panels -Individual Panels wired with accessory lights and plugs -Rewire Factory Harness	Bundle_Twall_52.5	1	\$14,451.00	\$14,451.00
	T148ext Full Wall Panel Kit Transit 148ext wall kit with doors Upholstered 3/8" ACX. L track @ top corner Anti-Mold treatment		1	\$8,495.00	\$8,495.00

Includes bamboo driver forward window sills.
Options to include cutouts for wall cubbies.
Add on a USB-C/USB-3 to the window sill +\$375

	Transit Wiring Harness Rewire		1	\$640.00	\$640.00
	Pull all the brake lights and cargo wires forward and re-route through frame				
	*Transit Wall Cubbies		2	\$799.00	\$1,598.00
	33" x 14" Transit Wall Cubby. Designed for easy mod to install Bunk Windows				
	Prewire Wall Circuit Harness		1	\$1,219.00	\$1,219.00
	14/2 to each wall panel for localized lights and 12V sockets. Spade Connectors 120V to rear driver and galley - Harwired 10AWG to secondary fuse block (opposite battery side) - Deutch Connector				
	Install Transit Wall Panel Kit		1	\$2,499.00	\$2,499.00
	Install T148 Wall package (Std and Extended) Ltrack Windowsills Connect Wall circuit to prewire				
12.	MightyMama Juicebox 480Ah LiFePO4, Alternator+Solar+Shore charging		1	\$15,400.00	\$15,400.00
	480Ah LiFePO4 2000W Victron Charge Inverter 40A Solar 50Amp Alternator Charging				
13.	Prewire Alternator DCDC harness	Prewire_Alt4	1	\$860.76	\$860.76
	1/0 from starter battery to house battery DC-DC charger 1/0 local frame ground Split loom under chassis Anderson Connector				
14.	Airtronic Heater Bundle for Transit (Installed)	Bundle_S3B4L_Transit_9		\$4,398.20	\$4,398.20
	Espar B4L gas airtronic heater with Rixen Enterprises Warranty. Tank Drop Includes Heat vent box -- standard black, bamboo available for +\$75 Please bring tank in close to empty.				
15.	Craftsman Water Box 22 Gallon		1	\$5,600.00	\$5,600.00
	22 Gallon Water Cabinet over the wheel well Low flow Shower Head ported to rear of box 1.2 GPM 20 Micron Filter Plumbing fixtures, fittings, and hoses Spray Port Quick Disconnect				
16.	Transit Grey Tank 20	Grey20_Transit_4	1	\$1,092.54	\$1,092.54
	Installed on Driver side				
17.	Outback Shower Hookup	OTB	1	\$1,102.15	\$1,102.15
	Outback shower installed on Craftsman Cabinet.				
18.	Bosch Water Heater (installed)	Bosch2.5_3	1	\$838.41	\$838.41
	Electric Hot Water Tank, 2.5 gal. Runs off inverter with a cutoff switch. Placed under sink				

19.	Jade Galley (Installed) Install Steelhead galley and fridge. Hook to prewiring and preplumbed Outback Shower.	Steelhead_2	1	\$6,826.50	\$6,826.50
	Steelhead Standard Galley Steelhead Standard Galley -Bamboo Countertop with Sink Insert -Food Grade cutting board finish -High Quality Laminate Construction -13"x13"x9" Stainless Sink [inside dimension] -Faucet / Soap Dispenser 36"x36"x21" Fits -86 Qt. Fridge -Two [6] Gallon Water Containers [Fresh/Grey] -Water Pump / Switch		1	\$4,995.00	\$4,995.00
	*Labor Standard Price per hour		5	\$165.00	\$825.00
	TruckFridge TF86 TruckFridge TF78 (TF86)		1	\$919.00	\$919.00
	TruckFridge TF86 Trim Flange TruckFridge TF86 Trim Flange & Shipping		1	\$87.50	\$87.50
20.	Elevation Station (Installed) Raising bed, installed and wired	Install_Elevation_21.5	1	\$8,662.00	\$8,662.00
21.	Solar on Rack (Installed) 400 w solar installed on a transit with an 8020 frame.	Solar_Rack_4	1	\$1,185.00	\$1,185.00
22.	Prewire Solar Harness SAE-deutch 10AWG 10AWG solar harness. Deutch disconnect to MPPT. SAE pass through installed on roof. Price reflected assumes no walls/ceiling	Prewire_Solar2	1	\$404.05	\$404.05
23.	Freedman GO-ES seat (Installed) The Freedman GoES gives 2 more seatbelts while flipping out of the way when not in use. Estimated for standard location behind driver seat, tank drop included. Custom Location will be based on actual time .	GoES_6	1	\$2,708.75	\$2,708.75
24.	Upper Cabinet (installed) 36 inch above galley (driver side) Upper cabinet installed in top corner Ltrack. Ltrack hardware and thumbscrews make this easy to move. Select from Sprinter/Transit ceiling shape.	UpperCab_Bundle_7	1	\$1,779.00	\$1,779.00
25.	Upper Cabinet (installed) 24 inch behind slider door Upper cabinet installed in top corner Ltrack. Ltrack hardware and thumbscrews make this easy to move. Select from Sprinter/Transit ceiling shape.	UpperCab_Bundle_7	1	\$1,734.00	\$1,734.00
26.	*Ford Transit Headliner Shelf Ford Transit Headliner Shelf	KIT- TraHeadShelf	1	\$850.00	\$850.00

27.	Transit Adventure Rig Exterior Bundle (Installed) Roof Rack Ladder Surf Pole to carry boards 270 Awning Front Light Bar Rear Flood Light	ExteriorBundle	1	\$11,048.50	\$11,048.50
	T148 CBMW Roof Rack Roof Rack from Cannonball Metal Works Transit 148 Long Standard opening for 2 fans Designed to work with OVS 270 awning Drop down for light bar in front Rear flood light mount plate		1	\$3,999.00	\$3,999.00
	*Labor Standard Install rack - Price per hour		6	\$165.00	\$990.00
	Side Ladder Cannonball Metalworks Custom Ladder, Powdercoated		1	\$800.00	\$800.00
	Surf Pole Surf Pole pairs with Ladder and Surf Hooks to store SUP and Surfboards on outside of van.		1	\$300.00	\$300.00
	Surf Pole Hook Mount point to rest SUP/surf board, with strap holes.		1	\$150.00	\$150.00
	*Labor Standard Install Ladder and Surf Accessories - Price per hour		3.5	\$165.00	\$577.50
	Prewire 2 Light Bars to Transit upfitter switches Prewire upfitter switches to SAE pass through plugs on roof. Standard 1 to front of roof, 1 to rear. For additional wire run, add \$250 per, up to 4 total. *Will dismantle dash and A pillar trim.		1	\$1,968.00	\$1,968.00
	Light Bar Component 52" Nilight - 15026C-A LED Light Bar 52Inch 300W Spot Flood Combo LED Driving Lamp Off Road Lights LED		1	\$99.00	\$99.00
	Porch Light 9" Leisure LED RV Exterior Porch Utility Light - 12v 1450 Lumen 9"		1	\$45.00	\$45.00
	OVS 270 awning		1	\$800.00	\$800.00
	*Labor Standard Install Awning - Price per hour		4	\$165.00	\$660.00
	*Labor Standard Install Light Bars - Price per hour		4	\$165.00	\$660.00
28.	Bugwall Screen (installed) Install Bugwall on slider door Sprinter or Transit	BugwallBundle_Slider2	1	\$729.00	\$729.00
29.	Transit Shade Package	Shades_TransitBundle	1	\$1,700.00	\$1,700.00

Vanmade Gear
Windshield
Front Windows
Slider door (VWD)
Driver 1st (Stock/Adwag)
2x Bunk Windows
2x Rear Doors

30.	Lagun Table Bundle	Bundle_Lagun1+	1	\$933.00	\$933.00
	The most versatile table on the market. 24x24 bamboo top. B Pillar Shark Mount Fold Down Plate				

31.	Transit Swivel Package	TSwivel_7	1	\$1,827.50	\$1,827.50
	Both front seat swivels for the Transit. If you have an electronic ebrake, labor goes down by 4 hours. Seat skirts get trimmed for clearance, up to metal structural bar				

Total	\$102,619.38
--------------	---------------------

Note to customer

Thank you for considering The VanLife Collective for your upcoming project. We've prepared an estimate that outlines the scope of work, labor, and products involved. If you have any questions or require further clarification or adjustments, please don't hesitate to reach out to us.

To proceed with the project, please follow these steps:

1. Return a signed copy of this estimate to info@thevanlifecollective.com
2. We will send you an invoice for deposit of 50% of the cost of the project.
(For larger custom projects with separate materials and time, we ask for 100% of materials and 50% of projected labor)
3. Upon payment of the deposit, we will schedule your project with consideration to your availability and our lead times.

We are excited about the prospect of working with you and are flexible to accommodate your schedule as needed.

Best regards,
The VanLife Collective Team