

# ESTIMATE

The Vanlife Collective  
1537-B Osprey Dr  
Hood River, OR 97031

info@thevanlifecollective.com  
+1 (541) 224-6966  
https://thevanlifecollective.com



## Template

**Bill to**  
Template

**Ship to**  
Template

### Estimate details

Estimate no.: 1318  
Estimate date: 02/06/2024

Vehicle Type, Height & Length: Transit High Roof  
148 Ext  
Vehicle Year: 2024  
Conversion Package: Family Jade

#	Date	Product or service	SKU	Qty	Rate	Amount
1.		<b>Summary</b> Family Jade Package on a Transit 148 Ext Seat 4 Sleep 4 2x Fans 2x Bunk windows 2x Large Slider windows Insulated Floor, Walls and Ceiling, upholstered and with Ltrack at the top corner where walls meet ceiling. Dimmable lights in ceiling, and reading lights at rear. Floor Trim Kit Prewire for lights and fans to standard wheel well location. 360Ah Juicebox battery system 400W Solar Steelhead Galley on Driver Side with Jerry Cans and 86Qt Fridge Elevation Station raising bed Espar Heater (4kw gas) Swivel Seats Shark Board B-Pillar Lagun Table Booth Bed Dinette with RoamRest Mattress and storage compartments More Storage: 2x Upper Cabinets, Headliner Shelf Outback Shower Bugwall Screen on slider door opening Vanmade Gear Window Shades all around		1	\$0.00	\$0.00
2.		<b>Foundation Floor T148std/S144</b> 3/4 Subfloor allows threaded anchors to integrate with our modular assemblies and saves time on the back end. Minicell insulation 3/4 anchored subfloor 2tec2 or Lonseal Flooring Anti-Mold treatment under subfloor Anti-Rust Treatment under anchor points Trim Kit for Step Cubby, Rear and Front edges, or reuse existing step and rear trim. (-\$150, removes extra trim pieces but adds time for building up step)	StdFloor_8	1	\$5,139.36	\$5,139.36
3.		<b>Thinsulate entire van</b>	Thins600L_6	1	\$1,601.00	\$1,601.00

600L Thinsulate throughout van.  
 Walls, ceiling, slider door and rear doors included.  
 Options to add on:  
 -Double layer (2x\$)  
 -Front doors (+\$450)  
 -Pull Through ceiling ribs (+\$300)

4.	<b>Ceiling -- Transit 148 ext (installed)</b> T148ext Split front panel 3x LED, dimmable, with blue night mode. Surface Mount Upholstered to your color choice Optional: add front glow strip +\$599 Standard Front/Rear fan locations optional		1	\$4,599.00	\$4,599.00
5.	<b>Elephant Ear Upholstery - Transit</b> Transit -- Upholster the foam "elephant ears"	Elephant_Transit_4	1	\$599.00	\$599.00
6.	<b>Prewire Lights</b> Prewire 12/2 to light run. Terminates in spade connector at ceiling, integrating with ceiling assembly. Central dimmer or switch optional	Prewire_lightrun2/2.5	1	\$341.88	\$341.88
7.	<b>Transit Wall Package</b> Install a full wall kit -Panels -Ltrack @ top corner -Prewire for panels -Individual Panels wired with accessory lights and plugs -Rewire Factory Harness	Bundle_Twall_52.5	1	\$14,451.00	\$14,451.00
	<b>T148ext Full Wall Panel Kit</b> Transit 148ext wall kit with doors Upholstered 3/8" ACX. L track @ top corner Anti-Mold treatment  Includes bamboo driver forward window sills. Options to include cutouts for wall cubbies. Add on a USB-C/USB-3 to the window sill +\$375		1	\$8,495.00	\$8,495.00
	<b>Transit Wiring Harness Rewire</b> Pull all the brake lights and cargo wires forward and re-route through frame		1	\$640.00	\$640.00
	<b>*Transit Wall Cubbies</b> 33" x 14" Transit Wall Cubby. Designed for easy mod to install Bunk Windows		2	\$799.00	\$1,598.00
	<b>Prewire Wall Circuit Harness</b> 14/2 to each wall panel for localized lights and 12V sockets. Spade Connectors 120V to rear driver and galley - Harwired 10AWG to secondary fuse block (opposite battery side) - Deutch Connector		1	\$1,219.00	\$1,219.00
	<b>Install Transit Wall Panel Kit</b> Install T148 Wall package (Std and Extended) Ltrack Windowsills Connect Wall circuit to prewire		1	\$2,499.00	\$2,499.00
8.	<b>Maxxfan 7500 smoke (Installed)</b> Fan Install Package.	Maxxfan7500_3	2	\$997.50	\$1,995.00

9.	<b>Airtronic Heater Bundle for Transit (Installed)</b> Espar B4L gas airtronic heater with Rixen Enterprises Warranty. Tank Drop Includes Heat vent box -- standard black, bamboo available for +\$75 Please bring tank in close to empty.	Bundle_S3B4L_Transit_9		\$4,398.20	\$4,398.20
10.	<b>Outback Shower Hookup</b> Outback shower plumbed through wall. Can be plumbed for propane heater on door or for Bosch hot coming from galley	OTB	1	\$1,102.15	\$1,102.15
11.	<b>Jade Galley (Installed)</b> Install Steelhead galley and fridge. Hook to prewiring and preplumbed Outback Shower.	Steelhead_2	1	\$7,731.50	\$7,731.50
	<b>Steelhead Standard Galley</b> Steelhead Standard Galley -Bamboo Countertop with Sink Insert -Food Grade cutting board finish -High Quality Laminate Construction -13"x13"x9" Stainless Sink [inside dimension] -Faucet / Soap Dispenser 36"x36"x21"  Fits -86 Qt. Fridge -Two [6] Gallon Water Containers [Fresh/Grey] -Water Pump / Switch		1	\$4,995.00	\$4,995.00
	<b>*Labor Standard</b> Price per hour		2	\$165.00	\$330.00
	<b>Confluence Plumbing</b> Add local plumbing to a galley 1.2 Gal pump 20 micron filter pump switch 6 gal fresh on CPC quick connect 6 gal grey		1	\$1,400.00	\$1,400.00
	<b>TruckFridge TF86</b> TruckFridge TF78 (TF86)		1	\$919.00	\$919.00
	<b>TruckFridge TF86 Trim Flange</b> TruckFridge TF86 Trim Flange & Shipping		1	\$87.50	\$87.50
12.	<b>Bunk Window (Installed)</b> Install a window in van body.	BunkWindow_3	2	\$844.94	\$1,689.88
13.	<b>Large Window (Installed)</b> Install a window in van body. --VWD Full Passenger Slider	LargeWindow	1	\$1,261.95	\$1,261.95
14.	<b>Large Window (Installed)</b> Install a window in van body. --VWD Full Driver Slider	LargeWindow	1	\$1,261.95	\$1,261.95
15.	<b>THE JUICEBOX -- 360AH Lithium</b> Drop-in Battery System, plug and play. Wiring connectors included for Alternator, Solar, Shore. Prewiring is additional	Juicebox360_24	1	\$10,912.00	\$10,912.00

240Ah is enough to power an induction stove, fridge, espar heater, computers, and smaller essentials.

16.	<b>Prewire Alternator DCDC harness</b> 1/0 from starter battery to house battery DC-DC charger 1/0 local frame ground Split loom under chassis Anderson Connector	Prewire_Alt4	1	\$965.96	\$965.96
17.	<b>Elevation Station (Installed)</b> Raising bed, installed and wired	Install_Elevation_21.5	1	\$8,662.00	\$8,662.00
18.	<b>Transit Solar (Installed)</b> 400 w solar installed on a transit with an 8020 frame.	Solar_Transit_5	1	\$1,619.94	\$1,619.94
19.	<b>Prewire Solar Harness SAE-deutch 10AWG</b> 10AWG solar harness. Deutch disconnect to MPPT. SAE pass through installed on roof. Price reflected assumes no walls/ceiling	Prewire_Solar2	1	\$404.05	\$404.05
20.	<b>Booth Bed Bundle (installed)</b> Booth Bed with Roam Rest Mattress. Transform your dining room into your bed	Bundle_Booth_14	1	\$6,049.00	\$6,049.00
	<b>*Booth Bed</b> Booth Bed Benches 2x Lagun tables that drop in to form connecting platform		1	\$4,469.00	\$4,469.00
	<b>Roamrest 4 Piece Mattress</b> RoamRest 4 piece mattress set 5 inch thick 3 stage foam		1	\$1,250.00	\$1,250.00
	<b>*Labor Standard</b> Price per hour		2	\$165.00	\$330.00
21.	<b>Freedman GO-ES seat (Installed)</b> The Freedman GoES gives 2 more seatbelts while flipping out of the way when not in use. Estimated for standard location behind driver seat, tank drop included. Custom Location will be based on actual time .	GoES_6	1	\$2,708.75	\$2,708.75
22.	<b>Upper Cabinet (installed)</b> 36 inch above galley (driver side) Upper cabinet installed in top corner Ltrack. Ltrack hardware and thumbscrews make this easy to move. Select from Sprinter/Transit ceiling shape.	UpperCab_Bundle_7	1	\$1,779.00	\$1,779.00
23.	<b>Upper Cabinet (installed)</b> 24 inch behind slider door Upper cabinet installed in top corner Ltrack. Ltrack hardware and thumbscrews make this easy to move. Select from Sprinter/Transit ceiling shape.	UpperCab_Bundle_7	1	\$1,734.00	\$1,734.00
24.	<b>*Ford Transit Headliner Shelf</b> Ford Transit Headliner Shelf	KIT- TraHeadShelf	1	\$850.00	\$850.00
25.	<b>Transit Swivel Package</b> Both front seat swivels for the Transit. If you have an electronic ebrake, labor goes down by 4 hours. Seat skirts get trimmed for clearance, up to metal structural bar	TSwivel_7	1	\$1,827.50	\$1,827.50

26.	<b>Shark Board B-Pillar Lagun Adaptor WITH LAGUN SLIVER BRACKET</b> Passenger Side Lagun B pillar mount	SharkSliver_1	1	\$169.00	\$169.00
27.	<b>Bugwall Screen (installed)</b> Install Bugwall on slider door Sprinter or Transit	BugwallBundle_Slider2	1	\$729.00	\$729.00
28.	<b>Transit Shade Package</b> Vanmade Gear Shades Windshield Front Windows Slider door (VWD) Driver 1st (Stock/Adwag) 2x Bunk Windows 2x Rear Doors	Shades_TransitBundle	1	\$1,700.00	\$1,700.00
				<b>Total</b>	<b>\$86,282.07</b>

### Note to customer

Thank you for considering The VanLife Collective for your upcoming project. We've prepared an estimate that outlines the scope of work, labor, and products involved. If you have any questions or require further clarification or adjustments, please don't hesitate to reach out to us.

To proceed with the project, please follow these steps:

1. Return a signed copy of this estimate to [info@thevanlifecollective.com](mailto:info@thevanlifecollective.com)
2. We will send you an invoice for deposit of 50% of the cost of the project.  
(For larger custom projects with separate materials and time, we ask for 100% of materials and 50% of projected labor)
3. Upon payment of the deposit, we will schedule your project with consideration to your availability and our lead times.

We are excited about the prospect of working with you and are flexible to accommodate your schedule as needed.

Best regards,  
The VanLife Collective Team