

ESTIMATE

The Vanlife Collective
1537-B Osprey Dr
Hood River, OR 97031

info@thevanlifecollective.com
+1 (541) 224-6966
https://thevanlifecollective.com



Template

Bill to
Template

Ship to
Template

Estimate details

Estimate no.: 1322
Estimate date: 02/15/2024

Vehicle Type, Height & Length: Transit High Roof
148 Long
Vehicle Year: 2024
Conversion Package: Standard Jade

#	Date	Product or service	SKU	Qty	Rate	Amount
1.		Summary Standard Jade on a Transit 148 Long Seat 2 Sleep 2 2x Fans Insulated Floor, Walls and Ceiling, upholstered and with Ltrack at the top corner where walls meet ceiling. Dimmable lights in ceiling, and reading lights at rear. Floor Trim Kit Prewire for lights and fans to standard wheel well location. 240Ah JuiceSqueeze over the wheel well battery system 400W Solar 21Gal Craftsman Water Cabinet Steelhead Galley on Driver Side Elevation Station raising bed Espar Heater (4kw gas)		1	\$0.00	\$0.00
2.		Foundation Floor T148std/S144 Minicell insulation 3/4 anchored subfloor 2tec2 or Lonseal Flooring Trim Kit	StdFloor_8	1	\$5,244.45	\$5,244.45
3.		Thinsulate entire van 600L Thinsulate throughout van. Walls, ceiling, slider door and rear doors included. Options to add on: -Double layer (2x\$) -Front doors (+\$450) -Pull Through ceiling ribs (+\$300)	Thins600L_6	1	\$1,601.00	\$1,601.00
4.		Ceiling -- Transit 148 std (installed) T148 and T148ext. Split front panel 3x LED, dimmable, with blue night mode. Surface Mount	CEILING_T148std_30	1	\$4,599.00	\$4,599.00

Upholstered to your color choice
Optional: add front glow strip +\$599

5.	Elephant Ear Upholstery - Transit Transit -- Upholster the foam "elephant ears"	Elephant_Transit_4	1	\$599.00	\$599.00
6.	Prewire Lights Prewire 12/2 to light run. Terminates in spade connector at ceiling, integrating with ceiling assembly. Central dimmer or switch optional	Prewire_lightrun2/2.5	1	\$341.88	\$341.88
7.	Transit Wall Package Install a full wall kit -Panels -Ltrack @ top corner -Prewire for panels -Individual Panels wired with accessory lights and plugs -Rewire Factory Harness	Bundle_Twall_52.5	1	\$14,151.00	\$14,151.00
	T148std Full Wall Panel Kit Transit 148std wall kit with doors. Upholstered 3/8" ACX. L track @ top corner Anti-Mold treatment Includes bamboo driver forward window sills. Options to include cutouts for wall cubbies. Add on a USB-C/USB-3 to the window sill +\$375		1	\$8,195.00	\$8,195.00
	Transit Wiring Harness Rewire Pull all the brake lights and cargo wires forward and re-route through frame		1	\$640.00	\$640.00
	*Transit Wall Cubbies 33" x 14" Transit Wall Cubby. Designed for easy mod to install Bunk Windows		2	\$799.00	\$1,598.00
	Prewire Wall Circuit Harness 14/2 to each wall panel for localized lights and 12V sockets. 120V to rear driver 10AWG to secondary fuse block (opposite battery side)		1	\$1,219.00	\$1,219.00
	Install Transit Wall Panel Kit Install T148 Wall package (Std and Extended) Ltrack Windowsills Connect Wall circuit to prewire		1	\$2,499.00	\$2,499.00
8.	JuiceSqueeze Battery Cabinet 240Ah Lithium 2000W Victron Charge Inverter Over the Wheel Well	JuiceS_33	1	\$13,200.00	\$13,200.00
9.	Prewire Alternator DCDC harness 1/0 from starter battery to house battery DC-DC charger 1/0 local frame ground Split loom under chassis Anderson Connector	Prewire_Alt4	1	\$965.96	\$965.96
10.	Maxxfan 7500 smoke (Installed) Fan Install Package. Front and Rear Fan	Maxxfan7500_3	2	\$997.50	\$1,995.00

11.	Elevation Station (Installed) Raising bed, fully installed	Install_Elevation_21.5	1	\$8,662.00	\$8,662.00
12.	Airtronic Heater Bundle for Transit (Installed) Espar S3B4L gas airtronic heater with Rixen Enterprises Warranty. Tank Drop Includes Heat vent box -- standard black, bamboo available for +\$75 Please bring tank in close to empty.	Bundle_S3B4L_Transit_9		\$4,398.20	\$4,398.20
13.	Prewire Solar Harness SAE-deutch 10AWG 10AWG solar harness. Deutch disconnect to MPPT. SAE pass through installed on roof. Price reflected assumes no walls/ceiling	Prewire_Solar2	1	\$404.05	\$404.05
14.	Transit Solar (Installed) 400 w solar installed on a transit with an 8020 frame.	Solar_Transit_5	1	\$2,155.57	\$2,155.57
15.	Craftsman Water Box 22 Gallon 22 Gallon Water Cabinet over the wheel well Driver Side Low flow Shower Head ported to rear of box 1.2 GPM 20 Micron Filter Plumbing fixtures, fittings, and hoses Spray Port Quick Disconnect		1	\$5,600.00	\$5,600.00
Total				\$63,917.11	

Note to customer

Thank you for considering The VanLife Collective for your upcoming project. We've prepared an estimate that outlines the scope of work, labor, and products involved. If you have any questions or require further clarification or adjustments, please don't hesitate to reach out to us.

To proceed with the project, please follow these steps:

1. Return a signed copy of this estimate to info@thevanlifecollective.com
2. We will send you an invoice for deposit of 50% of the cost of the project.
(For larger custom projects with separate materials and time, we ask for 100% of materials and 50% of projected labor)
3. Upon payment of the deposit, we will schedule your project with consideration to your availability and our lead times.

We are excited about the prospect of working with you and are flexible to accommodate your schedule as needed.

Best regards,
The VanLife Collective Team